

**BID TABULATION**  
**CITY OF BEAUMONT, TEXAS**  
**CATTAIL MARSH WETLAND REPAIR**  
**BID No. PW1121-06/ FEMA PROJECT No. 13339 & No. 39195**

**BID OPENING DATE: Thursday, January 7, 2021 @ 2:00 PM**

Item	Qty	Unit	Description	Solid Bridge Construction LLC 1204 Sam Houston Ave, Suite 1 Huntsville, TX 77340		McInnis Construction, Inc. 675 S. 4th Street Silsbee, TX 77656		Brystar Contracting, Inc. 8385 Chemical Rd. Beaumont, TX 77705		ALLCO, LLC 6720 College Street Beaumont, Texas 77707	
				Unit Price	Item Total	Unit Price	Item Total	Unit Price	Item Total	Unit Price	Item Total
BASE BID ITEMS											
1.	1	LS	<b>Mobilization</b> , including payment bond, performance bond, insurance, moving equipment to project, and demobilization, all in strict conformance with plans and specifications; NOT TO EXCEED 3% OF TOTAL PROJECT BID for,	\$10,000.00	\$10,000.00	\$20,500.00	\$20,500.00	\$30,000.00	\$30,000.00	\$35,000.00	\$35,000.00
2.	1	LS	<b>Exterior Slope Repair 1A</b> - repair the exterior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$4,503.00	\$4,503.00	\$9,602.50	\$9,602.50	\$5,000.00	\$5,000.00	\$16,733.17	\$16,733.17
3.	1	LS	<b>Exterior Slope Repair 1B</b> - repair the exterior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$8,255.00	\$8,255.00	\$20,462.50	\$20,462.50	\$12,000.00	\$12,000.00	\$23,109.39	\$23,109.39
4.	1	LS	<b>Exterior Slope Repair 1C</b> - repair the exterior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$12,587.00	\$12,587.00	\$34,572.50	\$34,572.50	\$22,000.00	\$22,000.00	\$29,443.43	\$29,443.43
5.	1	LS	<b>Exterior Slope Repair 1F</b> - repair the exterior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$9,010.00	\$9,010.00	\$26,275.00	\$26,275.00	\$14,000.00	\$14,000.00	\$32,915.70	\$32,915.70
6.	1	LS	<b>Exterior Slope Repair 2A</b> - repair the exterior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$1,742.00	\$1,742.00	\$4,935.00	\$4,935.00	\$2,500.00	\$2,500.00	\$17,299.86	\$17,299.86
7.	1	LS	<b>Exterior Slope Repair 2B</b> - repair the exterior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$10,083.00	\$10,083.00	\$26,002.50	\$26,002.50	\$13,000.00	\$13,000.00	\$27,699.97	\$27,699.97
8.	1	LS	<b>Exterior Slope Repair 2C</b> - repair the exterior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$3,982.00	\$3,982.00	\$9,185.00	\$9,185.00	\$4,500.00	\$4,500.00	\$17,861.86	\$17,861.86
9.	1	LS	<b>Exterior Slope Repair 4A</b> - repair the exterior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$3,350.00	\$3,350.00	\$7,625.00	\$7,625.00	\$4,000.00	\$4,000.00	\$17,380.30	\$17,380.30
10.	1	LS	<b>Exterior Slope Repair 4C</b> - repair the exterior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$24,107.00	\$24,107.00	\$70,172.50	\$70,172.50	\$36,000.00	\$36,000.00	\$47,163.87	\$47,163.87
11.	1	LS	<b>Exterior Slope Repair 5A</b> - repair the exterior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$7,778.00	\$7,778.00	\$22,115.00	\$22,115.00	\$12,500.00	\$12,500.00	\$28,784.88	\$28,784.88
12.	1	LS	<b>Interior Slope Repair 3A</b> - repair the interior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$6,979.00	\$6,979.00	\$16,932.50	\$16,932.50	\$8,000.00	\$8,000.00	\$26,252.26	\$26,252.26
13.	1	LS	<b>Interior Slope Repair 3B</b> - repair the interior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$9,501.00	\$9,501.00	\$27,367.50	\$27,367.50	\$15,000.00	\$15,000.00	\$33,174.15	\$33,174.15
14.	1	LS	<b>Interior Slope Repair 3C</b> - repair the interior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$17,274.00	\$17,274.00	\$50,295.00	\$50,295.00	\$27,000.00	\$27,000.00	\$44,279.50	\$44,279.50
15.	1	LS	<b>Interior Slope Repair 3D</b> - repair the interior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$5,701.00	\$5,701.00	\$15,167.50	\$15,167.50	\$7,500.00	\$7,500.00	\$25,919.01	\$25,919.01

**BID TABULATION**  
**CITY OF BEAUMONT, TEXAS**  
**CATTAIL MARSH WETLAND REPAIR**  
**BID No. PW1121-06/ FEMA PROJECT No. 13339 & No. 39195**

**BID OPENING DATE: Thursday, January 7, 2021 @ 2:00 PM**

Item	Qty	Unit	Description	Solid Bridge Construction LLC 1204 Sam Houston Ave, Suite 1 Huntsville, TX 77340		McInnis Construction, Inc. 675 S. 4th Street Silsbee, TX 77656		Brystar Contracting, Inc. 8385 Chemical Rd. Beaumont, TX 77705		ALLCO, LLC 6720 College Street Beaumont, Texas 77707	
				Unit Price	Item Total	Unit Price	Item Total	Unit Price	Item Total	Unit Price	Item Total
16.	1	LS	<b>Interior Slope Repair 3E</b> - repair the interior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$3,677.00	\$3,677.00	\$8,047.50	\$8,047.50	\$4,500.00	\$4,500.00	\$16,624.47	\$16,624.47
17.	1	LS	<b>Interior Slope Repair 3F</b> - repair the interior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$2,392.00	\$2,392.00	\$5,960.00	\$5,960.00	\$3,000.00	\$3,000.00	\$17,438.36	\$17,438.36
18.	1	LS	<b>Interior Slope Repair 4B</b> - repair the interior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$3,505.00	\$3,505.00	\$8,437.50	\$8,437.50	\$4,000.00	\$4,000.00	\$16,954.23	\$16,954.23
19.	1	LS	<b>Interior Slope Repair 4D</b> - repair the interior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$16,949.00	\$16,949.00	\$49,707.50	\$49,707.50	\$26,000.00	\$26,000.00	\$45,417.55	\$45,417.55
20.	1	LS	<b>Interior Slope Repair 4E</b> - repair the interior levee slope including removing vegetation, scarify existing levee slope 3" deep, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$10,977.00	\$10,977.00	\$32,997.50	\$32,997.50	\$15,500.00	\$15,500.00	\$43,794.15	\$43,794.15
21.	1	LS	<b>Interior Slope Repair 1D</b> - repair the interior levee slope including steel sheet pile coffer dam, removing vegetation, scarify existing levee slope 3" deep, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$26,242.00	\$26,242.00	\$87,135.00	\$87,135.00	\$420,000.00	\$420,000.00	\$293,102.26	\$293,102.26
22.	1	LS	<b>Interior Slope Repair 1E</b> - repair the interior levee slope including steel sheet pile coffer dam, removing vegetation, scarify existing levee slope 3" deep, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the repaired levee slope, all in accordance with the plans and specifications for	\$11,167.00	\$11,167.00	\$35,822.50	\$35,822.50	\$195,000.00	\$195,000.00	\$130,402.09	\$130,402.09
23.	1,190	LF	Install geotextile fabric and crushed limestone road material on the top of the finished berm, TEN FOOT (10') wide top of berm, all in accordance with the plans and specifications for	\$34.00	\$40,460.00	\$47.90	\$57,001.00	\$60.00	\$71,400.00	\$72.56	\$86,346.40
24.	2,354	LF	Install geotextile fabric and crushed limestone road material on the top of the finished berm, TWELVE FOOT (12') wide top of berm, all in accordance with the plans and specifications for	\$38.00	\$89,452.00	\$51.40	\$120,995.60	\$60.00	\$141,240.00	\$55.75	\$131,235.50
25.	1	LS	<b>Sampling Station</b> - construct outfall sampling station including reinforced concrete pad and fence post, relocate chain link fence, gate and cover, relocate sampler and electrical conduit/conductors, abandon existing pad, all in accordance with the plans and specifications for	\$20,900.00	\$20,900.00	\$34,940.00	\$34,940.00	\$18,000.00	\$18,000.00	\$17,792.24	\$17,792.24
26.	1	ALLOW	<b>Miscellaneous Improvements</b> - furnish all labor, materials, and equipment to perform all miscellaneous improvements, as directed by the Owner.	\$100,000.00	\$100,000.00	\$100,000.00	\$100,000.00	\$100,000.00	\$100,000.00	\$100,000.00	\$100,000.00
<b>ALTERNATE BID ITEMS</b>											
2A	1	LS	<b>Exterior Slope Mitigation 1A</b> - reconstruct the exterior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, construct 3' deep clay key, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$11,346.15	\$11,346.15	\$18,047.00	\$18,047.00	\$14,500.00	\$14,500.00	\$41,060.36	\$41,060.36
3A	1	LS	<b>Exterior Slope Mitigation 1B</b> - reconstruct the exterior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, construct 3' deep clay key, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$17,067.75	\$17,067.75	\$31,662.50	\$31,662.50	\$23,000.00	\$23,000.00	\$44,072.30	\$44,072.30
4A	1	LS	<b>Exterior Slope Mitigation 1C</b> - reconstruct the exterior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, construct 3' deep clay key, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$23,194.35	\$23,194.35	\$43,002.50	\$43,002.50	\$31,000.00	\$31,000.00	\$45,721.32	\$45,721.32

**BID TABULATION**  
**CITY OF BEAUMONT, TEXAS**  
**CATTAIL MARSH WETLAND REPAIR**  
**BID No. PW1121-06/ FEMA PROJECT No. 13339 & No. 39195**

BID OPENING DATE: Thursday, January 7, 2021 @ 2:00 PM

Item	Qty	Unit	Description	Solid Bridge Construction LLC 1204 Sam Houston Ave, Suite 1 Huntsville, TX 77340		McInnis Construction, Inc. 675 S. 4th Street Silsbee, TX 77656		Brystar Contracting, Inc. 8385 Chemical Rd. Beaumont, TX 77705		ALLCO, LLC 6720 College Street Beaumont, Texas 77707	
				Unit Price	Item Total	Unit Price	Item Total	Unit Price	Item Total	Unit Price	Item Total
5A	1	LS	<b>Exterior Slope Mitigation 1F</b> - reconstruct the exterior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, construct 3' deep clay key, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$27,412.50	\$27,412.50	\$50,750.00	\$50,750.00	\$37,000.00	\$37,000.00	\$47,989.78	\$47,989.78
6A	1	LS	<b>Exterior Slope Mitigation 2A</b> - reconstruct the exterior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, construct 3' deep clay key, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$8,428.10	\$8,428.10	\$15,500.00	\$15,500.00	\$11,500.00	\$11,500.00	\$36,837.78	\$36,837.78
7A	1	LS	<b>Exterior Slope Mitigation 2B</b> - reconstruct the exterior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, construct 3' deep clay key, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$31,112.15	\$31,112.15	\$62,547.50	\$62,547.50	\$46,000.00	\$46,000.00	\$67,333.88	\$67,333.88
8A	1	LS	<b>Exterior Slope Mitigation 2C</b> - reconstruct the exterior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, construct 3' deep clay key, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$11,661.10	\$11,661.10	\$22,865.00	\$22,865.00	\$16,600.00	\$16,600.00	\$37,929.77	\$37,929.77
9A	1	LS	<b>Exterior Slope Mitigation 4A</b> - reconstruct the exterior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, construct 3' deep clay key, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$10,431.50	\$10,431.50	\$17,690.00	\$17,690.00	\$12,600.00	\$12,600.00	\$36,550.25	\$36,550.25
10A	1	LS	<b>Exterior Slope Mitigation 4C</b> - reconstruct the exterior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, construct 3' deep clay key, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$56,692.00	\$56,692.00	\$133,617.50	\$133,617.50	\$98,000.00	\$98,000.00	\$74,704.86	\$74,704.86
11A	1	LS	<b>Exterior Slope Mitigation 5A</b> - reconstruct the exterior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, construct 3' deep clay key, reconstructing the exterior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$19,584.90	\$19,584.90	\$36,785.00	\$36,785.00	\$26,500.00	\$26,500.00	\$45,704.00	\$45,704.00
12A	1	LS	<b>Interior Slope Mitigation 3A</b> - reconstruct the interior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$19,241.95	\$19,241.95	\$31,752.50	\$31,752.50	\$23,200.00	\$23,200.00	\$42,646.09	\$42,646.09
13A	1	LS	<b>Interior Slope Mitigation 3B</b> - reconstruct the interior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$23,184.05	\$23,184.05	\$38,475.50	\$38,475.50	\$28,100.00	\$28,100.00	\$43,699.00	\$43,699.00
14A	1	LS	<b>Interior Slope Mitigation 3C</b> - reconstruct the interior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$39,394.00	\$39,394.00	\$75,155.00	\$75,155.00	\$55,200.00	\$55,200.00	\$56,507.06	\$56,507.06
15A	1	LS	<b>Interior Slope Mitigation 3D</b> - reconstruct the interior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$17,758.05	\$17,758.05	\$27,972.50	\$27,972.50	\$20,500.00	\$20,500.00	\$42,250.69	\$42,250.69

**BID TABULATION**  
**CITY OF BEAUMONT, TEXAS**  
**CATTAIL MARSH WETLAND REPAIR**  
**BID No. PW1121-06/ FEMA PROJECT No. 13339 & No. 39195**

**BID OPENING DATE: Thursday, January 7, 2021 @ 2:00 PM**

Item	Qty	Unit	Description	Solid Bridge Construction LLC 1204 Sam Houston Ave, Suite 1 Huntsville, TX 77340		McInnis Construction, Inc. 675 S. 4th Street Silsbee, TX 77656		Brystar Contracting, Inc. 8385 Chemical Rd. Beaumont, TX 77705		ALLCO, LLC 6720 College Street Beaumont, Texas 77707	
				Unit Price	Item Total	Unit Price	Item Total	Unit Price	Item Total	Unit Price	Item Total
16A	1	LS	<b>Interior Slope Mitigation 3E</b> - reconstruct the interior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$9,356.85	\$9,356.85	\$13,662.50	\$13,662.50	\$10,000.00	\$10,000.00	\$36,529.57	\$36,529.57
17A	1	LS	<b>Interior Slope Mitigation 3F</b> - reconstruct the interior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$8,203.60	\$8,203.60	\$11,840.00	\$11,840.00	\$8,500.00	\$8,500.00	\$36,807.39	\$36,807.39
18A	1	LS	<b>Interior Slope Mitigation 4B</b> - reconstruct the interior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$10,852.25	\$10,852.25	\$16,002.50	\$16,002.50	\$11,500.00	\$11,500.00	\$37,434.50	\$37,434.50
19A	1	LS	<b>Interior Slope Mitigation 4D</b> - reconstruct the interior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$43,076.00	\$43,076.00	\$77,517.50	\$77,517.50	\$57,000.00	\$57,000.00	\$57,216.79	\$57,216.79
20A	1	LS	<b>Interior Slope Mitigation 4E</b> - reconstruct the interior levee slope including removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, reconstructing the interior slope in compacted lifts, and hydro-mulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$33,619.85	\$33,619.85	\$58,842.50	\$58,842.50	\$43,000.00	\$43,000.00	\$55,206.20	\$55,206.20
21A	1	LS	<b>Interior Slope Mitigation 1D</b> - reconstruct the interior levee slope including including steel sheet pile coffer dam, removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, reconstructing the interior slope in compacted lifts, and hydromulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$203,967.00	\$203,967.00	\$155,330.00	\$155,330.00	\$510,000.00	\$510,000.00	\$293,819.83	\$293,819.83
22A	1	LS	<b>Interior Slope Mitigation 1E</b> - reconstruct the interior levee slope including including steel sheet pile coffer dam, removing existing crushed limestone and stockpile on-site, remove and dispose existing geotextile fabric, stripping the vegetation, removing a 2' layer of clay fill, reconstructing the interior slope in compacted lifts, and hydromulch seed the reconstructed levee slope, all in accordance with the plans and specifications for	\$67,019.35	\$67,019.35	\$50,237.50	\$50,237.50	\$225,000.00	\$225,000.00	\$193,861.65	\$193,861.65
<b>ADDITIVE BID ITEMS</b>											
27.	7,725	TON	<b>Interior Slope Protection</b> - furnish and install ROCK RIP-RAP, including filter fabric, in accordance with the plans and specifications for	\$116.00	\$896,100.00	\$51.88	\$400,773.00	\$103.00	\$795,675.00	\$96.41	\$744,767.25
28.	900	TON	<b>Outfall Channel Protection</b> - furnish and install ROCK RIP-RAP, without filter fabric, in accordance with the plans and specifications for	\$116.00	\$104,400.00	\$131.63	\$118,467.00	\$118.00	\$106,200.00	\$122.12	\$109,908.00
<b>BASE BID TOTAL (ITEMS 1-26)</b>				\$460,573.00		\$902,254.10		\$1,211,640.00		\$1,322,124.60	
<b>ALTERNATE BID TOTAL (ITEMS 1 + 23-26 + 2A-22A)</b>				\$953,415.45		\$1,322,691.60		\$1,669,340.00		\$1,744,257.21	
<b>ADDITIVE BID ITEM TOTAL (ITEMS 27-28)</b>				\$1,000,500.00		\$519,240.00		\$901,875.00		\$854,675.25	

**BID TABULATION**  
**CITY OF BEAUMONT, TEXAS**  
**CATTAIL MARSH WETLAND REPAIR**  
**BID No. PW1121-06/ FEMA PROJECT No. 13339 & No. 39195**

BID OPENING DATE: Thursday, January 7, 2021 @ 2:00 PM

Item	Qty	Unit	Description	Solid Bridge Construction LLC 1204 Sam Houston Ave, Suite 1 Huntsville, TX 77340	McInnis Construction, Inc. 675 S. 4th Street Silsbee, TX 77656	Brystar Contracting, Inc. 8385 Chemical Rd. Beaumont, TX 77705	ALLCO, LLC 6720 College Street Beaumont, Texas 77707
				Unit Price	Item Total	Unit Price	Item Total
			Aknowledge Addendum No. 1	Y	Y	Y	Y
			Aknowledge Addendum No. 2	Y	Y	Y	Y
			Aknowledge Addendum No. 3	Y	Y	Y	Y
			Required Forms Checklist	Y	Y	Y	Y
			Bid	Y	Y	Y	Y
			Bid Schedule	Y	Y	Y	Y
			Bid Summary	Y	Y	Y	Y
			Corporate Resolution	Y	Y	Y	Y
			Bid Bond	Y	Y	Y	Y
			Information Required of Bidder	Y	Y	Y	Y
			Conflict of Interest Questionnaire	Y	Y	Y	Y
			Statement of City Charter Provision of Conflict of Interest	Y	Y	Y	Y
			Insurance Requirement Affidavit	Y	Y	Y	Y
			MBE Schedule C	Y	Y	Y	Y
			House Bill 89	Y	Y	Y	Y
			Non-Collusion Form	Y	Y	Y	Y

The Bid Proposals submitted have been reviewed, and to the best of my knowledge this is an accurate tabulation of the Bids received.

Revised 1/14/21 to correct the ADDITIVE BID ITEM TOTAL (ITEMS 27-28)

Signature

*Jeffrey G. Beaver*

Date

1-14-21



February 3, 2021



Amalia "Molly" Villarreal, P.E.  
**City of Beaumont**  
City Engineer  
801 Main Street  
Beaumont, Texas 77701

Re: City of Beaumont  
Cattail Marsh Wetlands Repair  
Bid No. PW1121-06 / FEMA Project No. 13339 & No. 39195

Dear Ms. Villarreal,

Based on a review of the bids received Thursday, January 7, 2021 and the references of the low bidder, it is our recommendation that the above referenced project be awarded to **Solid Bridge Construction LLC** for Bid Items 1, 23 thru 26, and 2A thru 22A in the amount of \$953,415.45. See attached Bid Tabulation.

Sincerely,  
SCHAUMBURG & POLK, INC.



Jeffrey G. Beaver, P.E.