

BID TABULATION
CITY OF BEAUMONT, TEXAS
SPINDLETOP, FORREST & LONG, FRENCH ROAD,
M. L. KING, JR., AND VERONE LIFT STATIONS REHABILITATION
BID No. WU0121-13

BID OPENING DATE: Thursday, April 22, 2021 @ 2:00 PM

Item	Qty	Unit	Description	BDS Constructors LLC dba MK Constructors PO Box 1208 Vidor, TX 77662	
				Unit Price	Item Total
BASE BID ITEMS					
1.	1	LS	Mobilization , including payment bond, performance bond, insurance, moving equipment to project, and demobilization, all in strict conformance with plans and specifications; NOT TO EXCEED 3% OF TOTAL PROJECT BID for	\$26,103.00	\$26,103.00
2.	1	LS	Spindletop Lift Station Furnish all labor, equipment and materials to remove the existing pneumatic pumping system and existing bypass valve assembly & box, remove existing 4" influent pipe and replace with 6" influent pipe, furnish and install a new packaged grinder lift station including excavation, cement stabilized backfill, concrete foundation, 2" force main, all electrical power and control equipment, conduit & conductors, electrical connections, site restoration, bypass pumping and startup, all in accordance with the plans and specifications for	\$172,119.00	\$172,119.00
3.	1	LS	Forrest & Long Lift Station Furnish all labor, equipment and materials to remove the existing pneumatic pumping system and existing wet well, and construct a duplex submersible lift station including excavation, cement stabilized backfill, RCP wet well and valve vault, concrete top and bottom slabs, submersible pumps, guide rails, discharge pipe, fittings, valves, hatches, vent stack, 4" force main, new discharge manhole, all electrical power and control equipment, conduit & conductors, electrical connections, site restoration, bypass pumping and startup, all in accordance with the plans and specifications for	\$259,667.00	\$259,667.00
4.	1	LS	French Road Lift Station Furnish all labor, equipment and materials to remove the existing pneumatic pumping system and existing wet well, furnish and install a new packaged grinder lift station including excavation, cement stabilized backfill, concrete foundation, 2" force main, all electrical power and control equipment, conduit & conductors, electrical connections, site restoration, bypass pumping and startup, all in accordance with the plans and specifications for	\$143,241.00	\$143,241.00
5.	1	LS	M.L. King, Jr. Lift Station. Furnish all labor, equipment and materials to remove the existing pneumatic pumping system and existing wet well, furnish and install a new packaged grinder lift station including excavation, cement stabilized backfill, concrete foundation, 2" force main, all electrical power and control equipment, conduit & conductors, electrical connections, site restoration, bypass pumping and startup, all in accordance with the plans and specifications for	\$166,221.00	\$166,221.00
6.	1	LS	Verone Lift Station. Furnish all labor, equipment and materials to remove and replace the 4" DI pump discharge piping, fittings, check valves, and gate valves, coat all exposed piping including surface preparation, remove existing coating inside wet well, pressure wash and remove debris inside wet well, restore the wet well concrete surfaces to its original thickness and coat all interior concrete surfaces, and provide bypass pumping, all in accordance with the plans and specifications for	\$59,095.00	\$59,095.00
7.	1	ALLOW	Miscellaneous Repairs. Furnish all labor, materials and equipment to perform miscellaneous unforeseen work as directed by the Owner not to exceed	\$50,000.00	\$50,000.00
BASE BID TOTAL (ITEMS 1-7)				\$876,446.00	
Acknowledged Addendum No. 1				✓	
Required Forms Checklist				✓	
Bid				✓	
Bid Schedule				✓	
Bid Summary				✓	
Corporate Resolution				✓	
Information Required of Bidder				✓	
Conflict of Interest Questionnaire				✓	
Statement of City Charter Provisions on Conflict of Interest				✓	
Insurance Requirement Affidavit				✓	
MBE Schedule C				✓	
House Bill 89 (HB 89) Verification				✓	
FEMA Clauses for Construction Projects				✓	

*The Bid Proposals submitted have been reviewed, and to the best of my knowledge this is an accurate tabulation of the Bids received.

Signature

Date

